

L190 115 kV Transmission Line Asset Condition Refurbishment Project Presentation to the Energy Facility Siting Board

August 9, 2022 – East Greenwich

August 10, 2022 – South Kingstown

Agenda

- Rhode Island Energy™


- Introduction
- **Project Area**
- **Project Overview**
- Need
- Alternatives
- **Construction Sequence**
- Schedule
- **Community Outreach**
- **Impact Mitigation**
- **Project Impact**



View North - Stony Lane, North Kingstown

Project Area





Project Overview

- 12.5 miles from Davisville Tap to West Kingston No. 62 Substation.
- Line dates back to 1960s.
- Structures:
 - Replace 146 existing single-circuit wood H-frame and 3-pole structures with weathering steel pole (some poles in wet areas may be brown galvanized)
- Reconductor: 795 kcmil "Drake" ACSS from Davisville Tap to West Kingston No. 62 Substation, Old Baptist Tap (200 feet), and Tower Hill Tap North and South circuits (0.5 mile)
- Shield wire fiber optic ground wire






View to South – Waites Corner Rd, South Kingstown



Rhode Island Energy™

a PPL company





Project Need



- Asset condition refurbishment project is driven by the need to maintain a reliable system. The reliability is compromised by the following:
 - Pole top rot and aging
 - Several locations do not meet current insulation standards
- Project engineered with increased capacity to address thermal overloads identified in the ISO-NE's Eastern Connecticut (ECT) 2029 Need Assessment.
- Project includes addition of high-speed communications between substations via a dual purpose Optical Ground Wire (OPGW)

 –steel/aluminum ground wire with integrated fiber optics.



View to North - South Rd, East Greenwich

Alternatives



- No-Action Does not address the identified need.
- Parallel Transmission Line
- Railroad ROW
- Public Streets and Highways
- Underground Transmission Route Alternative
- Project (Preferred Option)

Construction Sequence

Rhode Island Energy™

- Removal of vegetation and Right of Way (ROW) mowing in advance of construction;
- Installation of soil erosion and sediment controls;
- Access road and work pad maintenance or construction;
- Installation of replacement structures;
- Transfer of existing conductors and OPGW;
- Removal and disposal of existing transmission line components;
- Replace existing conductors and OPGW; and
- Restoration of the ROW.



Schedule



ACTIVITY	ESTIMATED START DATE	ESTIMATED COMPLETION DATE
Planning and Engineering	Q2 2019	Q3 2022
Permitting and Licensing	Q1 2021	Q3 2022
Construction	Q4 2022	Q4 2024
Facilities In-Service	n-Service Q4 2024	
Final Restoration	Q2 2025	

Community Outreach




- Reviewed Project with Town officials
- Pre-construction outreach
 - Contacted abutters by mailing in advance of field survey and geotechnical work
- On-going outreach
 - Community Open House events;
 - Community outreach (e.g. door-to-door);
 - Project webpage;
 - Project hotline;
 - Fact sheets, door hangers, FAQs, timelines, etc.; and
 - Advertising.

Summary of Existing Natural and Social Environment



- Watershed and Waterways
- Soils
- Wetlands
- Rare Species
- Land Use
- Cultural and Historical Resources



View to the North - Oak Hill Road, North Kingstown

Impact Mitigation



- No long-term impacts to natural or social environment are expected.
- Any short-term impacts will be mitigated by use of soil erosion and sediment controls and best management practices (BMPs)
- An environmental monitor will ensure compliance with all regulatory programs and permit conditions

Project Impact



- Construction noise is expected to be intermittent
- Traffic impacts will be temporary
- No long-term impacts to residential, commercial or industrial land uses
- Disturbed areas will be restored to previously existing or improved condition





L190 115 kV Transmission Line Asset Condition Refurbishment Project