280 Melrose Street Providence, RI 02907 Phone 401-784-7288



February 8, 2023

### **VIA HAND DELIVERY & ELECTRONIC MAIL**

Luly E. Massaro, Commission Clerk Rhode Island Public Utilities Commission 89 Jefferson Boulevard Warwick, RI 02888

### RE: Docket No. 22-54-NG – The Narragansett Electric Company Proposed Fiscal Year 2024 Gas Infrastructure, Safety, and Reliability Plan <u>Responses to Division Data Requests – Division Set 3 (Complete Set)</u>

Dear Ms. Massaro:

I have enclosed an electronic version of Rhode Island Energy's<sup>1</sup> complete set of responses to the Division's Third Set of Data Requests in the above-referenced matter.<sup>2</sup> The Division has withdrawn DIV 3-9 in light of information provided in the Company's responses to other data requests.

Thank you for your attention to this matter. If you have any questions, please contact me at 401-316-7429.

Very truly yours,

in Burs Hills

Jennifer Brooks Hutchinson

Enclosure

cc: Docket 22-54-NG Service List Leo Wold, Esq. John Bell, Division Al Mancini, Division

<sup>&</sup>lt;sup>1</sup> The Narragansett Electric Company d/b/a Rhode Island Energy ("Rhode Island Energy" or the "Company").

<sup>&</sup>lt;sup>2</sup> Per communication from Commission counsel on October 4, 2021, the Company is submitting an electronic version of this filing followed by six (6) hard copies filed with the Clerk within 24 hours of the electronic filing.

### Certificate of Service

I hereby certify that a copy of the cover letter and any materials accompanying this certificate were electronically transmitted to the individuals listed below.

The paper copies of this filing are being hand delivered to the Rhode Island Public Utilities Commission and to the Rhode Island Division of Public Utilities and Carriers.

Gladd ede

Heidi J. Seddon

February 8, 2023 Date

# No. 22-54-NG- RI Energy's Gas Infrastructure, Safety and Reliability (ISR) Plan 2024 - Service List 2/6/2023

Name/Address	E-mail Distribution	Phone
The Narragansett Electric Company d/b/a Rhode Island Energy	<u>JHutchinson@pplweb.com;</u> COBrien@pplweb.com;	401-784-7288
Jennifer Hutchinson, Esq.	JScanlon@pplweb.com;   JMOBrien@rienergy.com;	_
Providence, RI 02907	PLaFond@rienergy.com;	_
Steve Boyajian, Esq.	SBriggs@pplweb.com;	401-709-3359
One Financial Plaza, 14th Floor Providence, RI 02903	JOliveira@pplweb.com;	_
	HSeddon@rc.com;	_
<b>Division of Public Utilities &amp; Carriers</b> Leo Wold, Esq.	Leo.Wold@dpuc.ri.gov; Margaret.l.hogan@dpuc.ri.gov;	401-780-2130
	Al.mancini@dpuc.ri.gov; John.bell@dpuc.ri.gov;	_
	Robert.Bailey@dpuc.ri.gov; Paul.roberti@dpuc.ri.gov;	
David Effron	ellen.golde@dpuc.ri.gov; Djeffron@aol.com;	603-964-6526
Berkshire Consulting 12 Pond Path North Hampton, NH 03862-2243		
Rod Walter, CEO/President Rod Walker & Associates	Rwalker@RWalkerConsultancy.com;	706-244-0894
	jwalker@rwalkerconsultancy.com;	

<b>Office of Energy Resources</b> Al Vitali, Esq.	Albert.vitali@doa.ri.gov;nancy.russolino@doa.ri.gov;Christopher.Kearns@energy.ri.gov;Shauna.Beland@energy.ri.gov;William.Owen@energy.ri.gov;Anika.Kreckel@energy.ri.gov;	
Office of Attorney General Nick Vaz, Esq. 150 South Main St. Providence, RI 02903	<u>nvaz@riag.ri.gov;</u>	401-274-4400 x 2297
<b>File an original and five copies</b> Luly E. Massaro, Commission Clerk Public Utilities Commission 89 Jefferson Blvd. Warwick RI 02888	Luly.massaro@puc.ri.gov;Patricia.lucarelli@puc.ri.gov;Todd.bianco@puc.ri.gov;Alan.nault@puc.ri.gov;Christopher.Caramello@puc.ri.gov;	401-780-2107

### Request:

For each month for the period January 1, 2019 through December 31, 2022, please provide by size and type of meter:

- a. The number of new meters installed by rate class in each month;
- b. The number of existing meters replaced by rate class in each month;
- c. The number of meters refurbished by month in each month;
- d. The number of meters retired from service by month in each month; and
- e. The number of meters in inventory at the end of each month.

### Response:

The Division of Public Utilities and Carriers withdrew this data request on January 23, 2023, in light the Public Utilities Commission's ruling at its Open Meeting on January 20, 2023.

Request:

Please provide the Company's projected inventory of meters at the end of CY 2024 by size and type of meter.

### Response:

The Division of Public Utilities and Carriers withdrew this data request on January 23, 2023, in light the Public Utilities Commission's ruling at its Open Meeting on January 20, 2023.

Request:

Please provide the expected useful lives for the Company's existing meters by size and type of meter.

### Response:

The Division of Public Utilities and Carriers withdrew this data request on January 23, 2023, in light the Public Utilities Commission's ruling at its Open Meeting on January 20, 2023.

### Request:

Please document and explain any differences in the times to obtain delivery of purchased meters by size and type of meter over the last 36 months.

### Response:

Over the past 36 months, the lingering effects of the COVID-19 pandemic on industry and resulting supply chain problems have increased lead times for gas meter and Encoder Receiver Transmitters ("ERT") orders from the Company's major suppliers. These suppliers identify semiconductor shortages and labor as their primary obstacles. During July of calendar year ("CY") 2021, one major supplier of 250-, 400-, 600-, and 1000-class meters, issued a memo notifying its major customers, including National Grid USA ("National Grid"), that they should expect delays in their shipping dates, which reflected labor and material shortages at the supplier. The supply chain issues began affecting another major supplier of residential meters, as well as the supplier of ERT modules required in the assembly of meters.

In late CY 2021 and early CY 2022, National Grid, and then Rhode Island Energy placed its purchase orders for the meters it would require in fiscal year ("FY") 2023. During CY 2022 and through early CY 2023, the delivery dates of purchase orders with all manufacturers were frequently delayed due to labor and material shortages. Some long-standing orders have been placed on hold without any new shipping update offered, due to the manufacturers' uncertainty in their own manufacturing capacity. Continuing volatility in the meter manufacturers' delivery schedules indicates these problems have not been resolved despite assurances from each manufacturer that they are working towards a solution.

A significant portion of gas meter and ERT orders placed in early January of CY 2022 for FY 2023 were delayed by the manufacturers over the course of the year as material and labor issues intensified. On average, delayed 250-class meter shipments have arrived or are currently scheduled to arrive 189 days after the ship date requested by National Grid on behalf of Rhode Island Energy, and 371 days after the initial placement of the purchase order. Larger meter classes including the 400-, 600-, and 1000- classes are experiencing delays of about 5 months beyond the requested delivery date. Similarly, delayed 275-class meters are scheduled to arrive an average of 332 days after the requested ship date and 540 days after the placement of the purchase order. These lengthy delivery times are a departure from prior years, where meter shipments could generally be expected to arrive when the manufacturer promised. Until the manufacturers become confident in their ability to produce and ship meters, they are reluctant to issue firm shipping schedules, so it is likely the issue will continue into the foreseeable future.

### Request:

Regarding all projects within the Reliability section of the Plan, please provide a simplified table containing each project, its cost per year, and its estimated in-service date ranked in order of highest priority to lowest priority.

### Response:

Please see Attachment DIV 3-5, for a project list by category. Each category lists projects in the order by which they are planned to be completed in FY 2024. Some categories anticipate reactive work which has yet to be identified or determined. In these instances, the project or category budget is listed as to-be-determined ("TBD").

There are often several factors that determine the order in which projects will be completed, starting with highest prioritization for safety and reliability. However, the order in which projects commence or how many projects are ongoing at once is also influenced by circumstances such as work readiness, the ability to permit the project, resource availability, and the funding/affordability to customers. The Company continually reviews all such factors to determine which project or projects should start next. Additionally, because there may be specified reasons for each category within the Reliability section and different pools of resources, the Company has provided a project list by category, rather than combining them all into a single Reliability category list.

#### System Automation

Project Name	Town	Project Type	In Service Year	FY 2024 12-Month (\$000)
101 Dyer St @ Pine St	Providence	Install System Automation	FY24	\$ 74
289 Point St @ Beacon Av	Providence	Install System Automation	FY24	\$ 95
642 Allens Ave	Providence	Install System Automation	FY24	\$ 130
518 Hartford Ave @ Petteys Ave	Providence	Install System Automation	FY24	\$ 90
71 Memorial Blvd @ Anna Dr	Newport	Install System Automation	FY24	\$ 92
135 Old Mill Ln 55#	Portsmouth	Install System Automation	FY24	\$ 44
70 Allendale Av @ George Waterman Av	Johnston	Install System Automation	FY24	\$ 99
300 Niantic Ave @ Pawnee St	Providence	Install System Automation	FY24	\$ 78
Edgar Ct Endpoint	Newport	Install System Automation	FY24	\$ 90
System Automation Total				\$ 792

#### Heater Installation Program

Project Name	Town	Project Type	In Service Year	FY 2024 12-Month (\$000)
Dey St GS (27 Dey St)	E Providence	Replace Heater	FY24	\$ 2,550
Smithfield GS (347 Putnam Pike)	Smithfield	Replace Heating System	FY24	\$ 1,950
Diamond Hill GS (4317 Diamond Hill Rd)	Cumberland	Replace Heating System	FY25	\$ 300
Miscellaneous Heater Upgrades	Portsmouth	Replace Fuel Train	FY25	\$ 56
Miscellaneous Heater Upgrades	Lincoln	Replace Fuel Train	FY25	\$ 25
Miscellaneous Heater Upgrades	Burriville	Replace Fuel Train	FY25	\$ 25
Miscellaneous Heater Upgrades	Providence	Purchase BMS	FY25	\$ 100
Heater Installation Program Total				\$ 5,006

#### Heaters Replacement and Ownership Transfer

Project Name	Town	Project Type	In Service Year		FY 2024 12-Month (\$000)
Tiverton GS (400 Main Rd)	Tiverton	Replace Take Station	FY24	\$	190
Heaters Replacement and Ownership Transfer Total					190

#### Take Station Refurbishment

Project Name	Town	Project Type	In Service Year	FY 2024 12-Month (\$000)
Smithfield GS (347 Putnam Pike) Phase 1	Smithfield	Replace 35 PSIG Station	FY24	\$ 839
Smithfield GS (347 Putnam Pike) Phase 2	Smithfield	Replace 99 PSIG Station	FY25	\$ 100
Miscellaneous Take Station Enhancement	All	Odorization and Generator upgrades	FY24	\$ 225
Take Station Refurbishment To	tal			\$ 1,164

#### **Pressure Regulating Facilties**

Project Name	Town	Project Type	In Service Year	FY 2024 12-Month (\$000)
Park Av @ Maple Av	Cranston	Replace Station	FY24	\$ 950
Smith St @ Sunset Av	North Providence	Replace Station	FY24	\$ 850
Mendon Rd @ Nate Whipple Hwy #1	Cumberland	Replace Station	FY24	\$ 600
Station St @ Pond St	Cranston	Replace Station	FY24	\$ 850
337 Lonsdale Av	Pawtucket	Replace Station	FY24	\$ 850
Wellington St @ Thames St LP	Newport	Replace Station	FY25	\$ 45
Weeden St @ Smithfield Av	Pawtucket	Replace Station	FY25	\$ 30
New River Rd @ Cottage St	Lincoln	Replace Station	FY25	\$ 30
Mendon Rd @ Nate Whipple Hwy #2	Cumberland	Replace Station FY25		\$ 60
110 Atwood Av @ D St	Cranston	Replace Station	FY25	\$ 250
235 Promenade St @ Kingsley Av	Providence	Abandon Station	FY25	\$ 45
Post Rd @ 265 Byron Blvd	Warwick	Abandon Station	FY25	\$-
Walcott Av @ St Georges	Middletown	Abandon Station	FY25	\$-
1584 Plainfield St @ Plainfield Pk	Cranston	Replace Station	FY25	\$ 250
Wellington St @ Thames St 40 PSIG	Newport	Replace Station	FY25	\$ 125
3362 Kingstown Rd (Waites Corner)	North Kingstown	Install Bypass Valve	FY24	\$ 50
Mayfield Rd @ Oakland Av	Cranston	Install Bypass Valve	FY24	\$ 50
Dyer St @ Pine St	Providence	Install Bypass Valve	FY24	\$ 40
Stony Ln @ Rt 2	North Kingstown	Install Bypass Valve	FY25	\$ 25
259 Wamp Tr @ Boyd Av	East Providence	Install Bypass Valve	FY25	\$ 25
228 Carroll Av @ Ocean Dr	Newport	Install Bypass Valve	FY25	\$ 25
71 Corina St @ Glasgow St	Providence	Install Bypass Valve	FY25	\$ 50
Pressure Regulating Facilties Total				\$ 5,200

## Valve Installation/Replacement - Primary Valve Program & Aquidneck Island Low Pressure Valves

Project Name	Town	Project Type	In Service Year	FY 2024 12-Month (\$000)
Champlin @ Rhode Island Ave 6"	NPR	primary valve install	FY24	\$ 20
Thames St @ W Narragansett 12"	NPR	primary valve install	FY24	\$ 24
Thames St @ Washington 12"	NPR	primary valve install	FY24	\$ 23
Thames St @ Brewer 16"	NPR	primary valve install	FY24	\$ 539
Valve Installation/Replacement Total	\$ 606			

#### Gas System Reliability

Project Name	Town	Project In Service Type Year		FY 2024 12-Month (\$000)
163-200 Sunbury St LP-35#	PVD	LP Elimination	FY24	\$ 136
LNC Old River Rd, Manville (LP-99	LNC	Single Feed Elimination	FY24	\$ 667
LNC Beverly Dr (LP-99)	LNC	LP Elimination	FY25	\$ 318
NPV 1-26 Borah St (LP-to-60)	NPV	LP Elimination	FY25	\$ 15
WSO Diamond Hill Rd-Dewey St (60)	WSO	LP Elimination	FY25	\$ 30
WWK East Av/Bald Hill Rd SFE	WWK	Single Feed Elimination	FY24	\$ 700
Cannon St CRA	CRA	Single Feed Elimination	FY24	\$ 654
NPR (10-to-35) P1-3	NPT	System Integration	FY25	\$ 10
Gas System Reliability Total				\$ 2,530

I&R

#### I&R - Reactive

Location	Town	Project Type	In Service Year	FY 2024 12-Month (\$000)
Portsmouth Gate Odorizer	Portsmouth	Reactive Work	FY24	\$ 76
TBD – Reactive Work	TBD	Reactive Work	FY24	\$ 1,326
I&R - Reactive Total				\$ 1,402

#### **Distribution Station Over Pressure Protection**

Project Name	Town	Project Type	In Service Year	FY 2024 12-Month (\$000)
101 North Broadway @ Greenwood Av	East Providence	Install Control Lines Header	FY24	\$ 275
18 Maple @ Yarnell Ave	Middletown	Install Control Lines Header	FY24	\$ 385
888 Wellington Ave @ Well Ave	Cranston	Install Control Lines Header	FY24	\$ 275
22 Depot Ave @ Cranston St	Cranston	Install Control Lines Header	FY24	\$ 400
Asylum St @ Mason St	Woonsocket	Install Control Lines	FY24	\$ 136
Charles St @ Mineral Spring Ave	North Providence	Install Control Lines Header	FY24	\$ 375
Moshassuck St @ Main St	Pawtucket	Install Control Lines Header	FY24	\$ 274
642 Allens Ave	Providence	Install Relief Valve		\$ -
Control Line Header 1	TBD	Install Control Lines Header	FY25	\$ 150
Control Line Header 2	TBD	Install Control Lines Header	FY25	\$ 150
Distribution Station Over Pressure Protection	\$ 2,420			

#### LNG

Project Name	Town	Project Type	In Service Year	FY 2024 12-Month (\$000)
LNG - OML Portable Equipment	Middletown/ Portsmouth	Portable Equipment	FY26	\$ 2,511
LNG - Cumberland Supplemental Portable Storage	Cumberland	Portable Equipment	FY25	\$ 875
LNG - Exeter Boiloff Compressor 2 Upgrade	Exeter	Boiloff Compressor Upgrade	FY24	\$ 7,474
LNG - Cumberland LNG Water Main	Cumberland	Water Main Installation	FY24	\$ 750
LNG - Exeter HMI Hardware & Software Upgrade	Exeter	Hardware & Software Upgrade	FY24	\$ 28
LNG - Exeter Control Room Upgrade with Offices, Backup Gas Control, Bathrooms/Showers, Attached Shop	Exeter	Control Room Upgrade	FY25	\$ 1,111
LNG - Exeter Truck Station Upgrade with plant AESD Upgrade	Exeter	Truck Station Upgrade	FY26	\$ 500
LNG - Cumberland Portable Vaporizer Tap	Cumberland	Portable Equipment Infrastructure	FY24	\$ 400
LNG - Exeter Emergency Generator Upgrade & UPS	Exeter	Site Upgrade	FY25	\$ 78
LNG - Exeter LNG Septic Upgrade	Exeter	Site Upgrade	FY24	\$ 875
LNG - Exeter Critical Spares	Exeter	Critical Spares	FY24/FY25	\$ 113
LNG - Cumberland Critical Spares	Cumberland	Critical Spares	FY24/FY25	\$ 113
LNG - Cumberland BOG Recovery Manifold	Cumberland	Portable Equipment Infrastructure	FY24	\$ 250
LNG - Newport Navy Yard Site	Newport	Demo / Retirement	FY26	\$ 281
LNG - Exeter Tank Switchback Stairs	Exeter	Safety	FY25	\$ 333
LNG - Blanket	All Locations	Blanket	FY24/FY25	\$ 572
LNG - Exeter Hi Ex Foam System	Exeter	Hi Ex Foam System	FY24	\$ 50
LNG - Cumberland Portable LNG Equipment	Cumberland	Portable Equipment	FY24	\$ 6
LNG Total				\$ 16,319

#### **Replace Pipe on Bridges**

Project Name	Town	Project In Service Type Year			FY 2024 12-Month (\$000)	
Mineral Spring Av, N Providence	N Providence	Main Replacement on bridge	FY24	\$	\$ 600	
Sylvan Dr Bridge main abandonment, E Greenwich	E Greenwich	Main Abandonment and Main extension	FY24	\$	200	
Lonsdale Ave Bridge, PAW	Pawtucket	Main Replacement on bridge	FY24	\$	260	
Atwells Av Bridge, Providence	Providence	Main Abandonment	FY24	\$	140	
Goat Island Bridge, Newport	Newport	Main Replacement on bridge	FY25	\$	50	
Glenbridge Ave Bridge, Providence	Providence	Main Relocation on bridge	FY25	\$	50	
River St Bridge, Woonsocket	Woonsocket	Abutment Wall	FY25	\$	50	
Replace Pipe on Bridges Total					1,350	

#### **Access Protection Remediation**

Project Name	Town	Project Type	In Service Year	FY 2024 12-Month (\$000)	
Schooner Dr, Tiverton (BTIV-0001)	Tiverton	Install Access Protection Barrier	FY24	\$ 20	
Esmond Mill Dr, Smithfield (SMF-0012)	Smithfield	Install Access Protection Barrier	FY24	\$ 20	
Great Rd, Union Village Railroad Bridge, N Smithfield (BNSF-0003)	N Smithfield	Install Access Protection Barrier	FY24	\$ 20	
Access Protection Remediation Total	\$ 60				

#### **Tools & Equipment**

Project Name	Town	Project Type	In Service Year	FY 2024 12-Month (\$000)
TD Williamson Pro-stop	N/A	Equipment Purchase	FY24	\$ 522
Ground Penetrating Radar - GPR	N/A	Equipment Purchase	FY24	\$ 67
Meter Testing Equipment	N/A	Equipment Purchase	FY24	\$ 110
TBD - General Capital Tools & Equipment	N/A	Equipment Purchase	FY24	\$ 918
Tools & Equipment Total	\$ 1,617			

#### Weld Shop

Location	Town	Project Type	In Service Year	FY 2024 12-Month (\$000)
Allens Ave	Providence	Facility	FY24	\$ 8,860
Weld Shop Total				\$ 8,860

### Request:

The Company has informed the Division that it is in the process of completing a data scrub of its gas pipe infrastructure and will be implementing a new software system for its gas distribution system. Provide the following:

- a. Name and description of the new software;
- b. Date of implementation of the new software; and
- c. How is the Company addressing inconsistencies within the current data system? Please explain.

### Response:

- a.) The new software being implemented is a product of JANA Corporation. It is called "Lighthouse Distribution Integrity Management Platform." This software evaluates the Company's assets and assigns predefined risk units to each based upon various operating factors such leak history, material, age, etc. to determine a Probability of Failure ("PoF"). Furthermore, the software evaluates the Consequence of Failure ("CoF") by evaluating the health and safety impacts, economic loss, regulatory / corporate reputational impacts and environmental impacts. The total risk is calculated by multiplying the PoF x CoF. This is used to identify the riskiest assets within the system as well as grouping assets to identify areas where the Company could maximize its risk elimination by focusing on neighborhoods or regions for replacement.
- b.) The new software is currently scheduled for deployment in October 2023.
- c.) The Company is addressing inconsistencies by working directly with the vendor to create default rules to apply when specific information is missing. An example of a rule developed was to address missing polyethylene pipe information. By providing a history of the pipe types used by the legacy gas companies in Rhode Island, by date, size, and type, if a section of pipe from a specific town, date, and size is flagged in the asset database, the algorithm built into the risk model can perform a comparison to the table and extract the missing information.

Request:

Regarding DR 1-8, please clarify what led to the length of main installed being lower than length of main abandoned. Is this due to rerouting, or something else? Please explain.

### Response:

The three phases of the Middletown low pressure elimination project have a total of approximately 22,600 feet of main installation, and an abandonment of 22,805 feet of main. The 205 foot difference in main is due to not requiring the mains to be extended as far to the services at extremities. There is a 99# main already installed in Wolcott Avenue, Briarwood Avenue, and other side streets that have parallel low pressure mains. Transferring the services from the low pressure mains to the 99# mains will allow the abandonment of these low pressure mains without the need for additional new main installation.

Please note that these numbers are approximate lengths of proposed main, so the 205 foot discrepancy could be even less when the mains are installed.

Request:

Regarding the \$7,100 cost per service provided in DR 1-24, please identify primary cost drivers for the increase.

### Response:

The \$7,100 unit cost stated in the Company's response to Division 1-24 was derived using a simple formula that divided the partial year total accumulated costs by the number of units completed as of the date of the response. This unit cost included spending on restoration for services completed in the previous year. Therefore, the partial year unit cost, along with restoration costs associated with previous fiscal year service replacement, was skewed higher than the long term average.

The Company is proposing a Proactive Service Replacement budget of \$0.559 million for the FY 2024 (12-month) period for a target of 100 service replacements. The unit cost in this budget proposal is \$5,590 and is based upon the average unit costs for all Proactive Service Replacements from FY 2021 to present when incorporating all costs associated with the service replacement and final restoration.

### Request:

Regarding the proposed Weld Shop facility, please describe non-ISR related work (if any) that the Company expects to occur at this facility.

### Response:

The Company's main operations objective for the Weld Shop facility is to support capital projects within the Gas ISR program. Almost all of operations work ("OPEX") is done in the field, where the specific asset is located, meaning the work is not performed in a Weld Shop. Of the work that welders perform, approximately 95% is Capital and 5% is OPEX. The Company estimates that less than 5% of the OPEX specific work, or less than 1% of the welders' overall work, could be brought into the Weld Shop versus completing it all in the field. Thus, the Company expects that less than 1% of work to be performed in the Weld Shop will be non-ISR related work.

### Request:

Regarding the proposed Weld Shop please describe:

- (a) The larger welding fabrications in-house the Company anticipates undertaking and provide documentation of these projects; and
- (b) All larger welding fabrications that the Company outsourced within the last three years that the Company could have handled had the Company had the Weld Shop.

### Response:

- (a) Fabrication of steel parts for any Gas ISR Plan project, large or small, can be completed in the new facility. The weld shop is currently being designed to have a large enough footprint capable of completing the Company's regulator pits and vault projects. The weld shop would allow internal welders the ability to work on the Company's larger piping within the system. From a practical standpoint, the welders are currently limited to piping under 12-inch-diameter because of the size and weight of the pipe. Thus, welding on larger diameter pipe for projects have not been completed internally because of space limitations. Additionally, projects that require multiple similar pieces have not been completed internally due to space/temporary storage constraints.
- (b) The Company does not have a list of all larger welding fabrications that it has outsourced within the last three years that it could have handled in-house if it had the weld shop. However, an example of those larger fabrications include piping that was prefabricated for the Southern Rhode Island Gas Expansion Project. Additionally, the Company has prefabricated regulator pits and vaults off site utilizing external resources and had them delivered and installed on-site. The welding of CISBOT fittings and large steel fittings for Main Replacement projects could also have been done in-house, instead of being outsourced to contractors. Multimeter header spools are currently contracted out to vendors leading to higher costs because of shipping/handling and the possibility for material wastage due to custom site corrections for each job. The Company anticipates the weld shop will provide in-house resources with a facility that can handle all assets within the system, including the examples provided above.

Request:

Please provide the FY 2023 Gas Infrastructure, Safety, and Reliability Plan Quarterly Update – Third Quarter Ending December 31, 2022.

Response:

Please see the table below which is the Attachment B – Breakout that will be included in the FY 2023 Gas ISR Plan Quarterly Update – for the Third Quarter Ending December 31, 2022. This will be filed with the Public Utilities Commission and the Division of Public Utilities and Carriers on or around February 15, 2023. Attachment B – Breakout provides the fiscal year to date budget versus actual spending and the overall FY 2023 budget versus full year spending forecast.

### The Narragansett Electric Company d/b/a Rhode Island Energy RIPUC Docket No. 22-54-NG In Re: Proposed FY 2024 Gas Infrastructure, Safety and Reliability Plan Attachment DIV 3-12

Attachment B - Breakout

#### The Narragansett Electric Company d/b/a Rhode Island Energy - RI Gas Capital Spending by Investment Categories - Detail FY 2023 through December 31, 2022 (\$000)

	FYTD			FY 2023 - Total			
Categories	Budget	Actual	Variance	Budget	Forecast	Variance	
NON-DISCRETIONARY							
Public Works							
CSC/Public Works - Non-Reimbursable	\$18,151	\$11,825	(\$6,326)	\$20,596	\$14,362	(\$6,234)	
CSC/Public Works - Reimbursable	\$1,322	\$1,808	\$485	\$1,437	\$1,937	\$500	
CSC/Public Works - Reimbursements	(\$1,089)	(\$2,980)	(\$1,891)	(\$1,433)	(\$4,300)	(\$2,867)	
Public Works Total	\$18,384	\$10,652	(\$7,732)	\$20,600	\$11,999	(\$8,601)	
Mandated Programs		4			4	4-	
Corrosion	\$861	\$1,110	\$248	\$1,305	\$1,305	\$0 (64.242)	
Purchase Meter (Replacement)	\$3,936	\$3,520	(\$416)	\$5,248	\$3,935	(\$1,313)	
Sanvica Banlacament (Baactiva) - Non-Leaks(Other	\$7,811	\$5,748 \$1.760	(\$2,064) (\$1,284)	\$10,100	\$7,600	(\$2,500)	
Main Replacement (Reactive) - Maintenance (incl Water Intrusion)	\$5,140 \$925	\$1,702	(\$1,564) (\$02)	\$1,097	\$2,447	\$/50 (\$2,000)	
Low Pressure System Elimination (Proactive)	\$1.700	\$90 \$90	(\$1,610)	\$3,000	\$390	(\$1,610)	
Transmission Station Integrity	\$2,896	\$100	(\$2,796)	\$4,510	\$180	(\$4,330)	
Pipeline Integrity - IVP - Wampanoag Trail Pipeline Replacement	\$350	\$6	(\$344)	\$500	\$80	(\$420)	
Mandated Total	\$21,626	\$13,169	(\$8,456)	\$28,360	\$16,937	(\$11,423)	
Damage / Failure (Reactive)							
Damage / Failure (Reactive)	\$19	\$12	(\$7)	\$25	\$12	(\$13]	
NON-DISCRETIONARY TOTAL	\$40.028	\$73 833	(\$16 195)	\$48.985	\$78.948	(\$20.037)	
DISCRETIONARY	<b>9</b> <del>4</del> 0,020	723,033	(\$10,155)		720,J <del>4</del> 0	(\$20,037)	
Proactive Main Replacement							
Main Replacement (Proactive) - Leak Prone Pipe	\$69,168	\$72,676	\$3,508	\$75,204	\$81,083	\$5,879	
Main Replacement (Proactive) - Large Diameter LPCI Program	\$2,250	\$4,298	\$2,048	\$2,250	\$3,868	\$1,618	
Atwells Avenue	\$1,244	\$2,719	\$1,475	\$1,464	\$3,085	\$1,621	
Proactive Main Replacement Total	\$72,662	\$79,693	\$7,031	\$78,918	\$88,036	\$9,118	
Proactive Service Replacement							
Proactive Service Replacement Total	\$564	\$158	(\$406)	\$600	\$158	(\$442)	
Reliability							
System Automation	\$664	\$485	(\$179)	\$800	\$800	\$0	
Heater Installation Program Heater Installation Program	\$968	\$609	(\$359)	\$1,242	\$953	(\$289)	
Heater Instantation Frogram - wampunoag Trait Heaters Replacement and Ownership Transfer	\$4,088 ¢c. 271	\$4,972	\$884 (\$2,202)	\$4,349	\$5,135	\$/86 (¢1,550)	
Allens Ave Multi Station Rebuild	\$0,371 ¢0	\$4,069 ¢052	(\$2,303) ¢052	\$7,585	\$0,035 \$1.09E	(\$1,550) \$1,095	
Take Station Refurbishment	90 \$840	\$736	(\$104)	\$1 150	\$1,085	\$1,065 \$9	
Take Station Enhancement Program -Tiverton GS Ownership Transfer	\$4 257	\$3,673	(\$584)	\$4 529	\$5 423	\$894	
Valve Installation/Replacement (incl Storm Hardening & Middletown/Newport)	\$857	\$23	(\$834)	\$988	\$50	(\$938)	
Gas System Reliability	\$2,836	\$245	(\$2,591)	\$3,260	\$382	(\$2,878)	
I&R - Reactive	\$963	\$1,234	\$271	\$1,375	\$1,375	\$0	
Distribution Station Over Pressure Protection	\$2,340	\$2,070	(\$270)	\$3,000	\$2,400	(\$600)	
LNG	\$8,259	\$7,970	(\$289)	\$10,089	\$8,716	(\$1,373)	
LNG - Portable Equipment Purchase	\$0	\$1,421	\$0	\$0	\$7,000	\$7,000	
Replace Pipe on Bridges	\$675	\$169	(\$506)	\$900	\$200	(\$700)	
Access Protection Remediation	\$54	\$124	\$69	\$272	\$172	(\$100)	
Tools & Equipment		\$1,309	\$604	\$824	\$1,687	\$863	
Weld Shop		\$0	\$0	\$0	\$3,000	\$3,000	
Reliability Total	\$33,879	\$30,062	(\$3,816)	\$40,363	\$45,573	\$5,210	
SUBIOTAL DISCRETIONARY (WILDOUT GAS EXPANSION)	\$107,105	\$109,913	\$2,808	\$119,881	\$133,767	\$13,886	
Pinalina	¢520	\$406	(\$24)	ŚGOO	\$5 <i>1</i> 0	(\$60)	
Other Upgrades/Investments	\$306	\$490 \$1	(\$24)	\$396	\$J40 \$15	(\$00)	
Regulator Station Investment		\$3 322	(\$1 714)	\$5 793	\$3 913	(\$1,880)	
Southern RI Gas Expansion Project Total		\$3.819	(\$2.044)	\$6.789	\$4.468	(\$2,321)	
DISCRETIONARY TOTAL (With Gas Expansion)		\$113,732	\$765	\$126,670	\$138,235	\$11,565	
CAPITAL ISR TOTAL (Base Capital - Without Gas Expansion)	\$147,133	\$133,746	(\$13,387)	\$168,866	\$162,714	(\$6,152)	
CAPITAL ISR TOTAL (With Gas Expansion)	\$152.995	\$137.565	(\$15,430)	\$175.655	\$167,183	(\$8.472)	
	<i>4_32,333</i>	÷_0,,000	(+10)+30)	<i>\</i>	<i>\07,100</i>	(70)772	
Additional Capital Investments (Not currently included in the ISR)							
Aquidneck Island Long Term Capacity Options	\$0	\$39	\$39	\$1,000	\$39	(\$961)	
INC Combined Tends of the second seco	ć1 075	622	161 0521	éa 500	ć220	(62.270)	